

PEZZIMENTI TUNNELBORE



Specialising in: **Highly Accurate, Laser-Guided Microtunnels.**

Harrington Grove





To gravity drain a large residential development, a series of long distance microtunnels at depths up to 13m were required to house the 225mm sewer pipes.

+ 3 x Single Drive Microtunnels

Killard Excavation won the head contract and excavated the drilling shafts. All 3 microtunnels were completed as single drives from the downstream end of each bore. There was little ground water moisture which allowed most of the 580m to be microtunnelled without any added water.

The production rate ranged between 20 and 30 m per day. Including set up and pipe pushing the project took 9 weeks from mid July to mid September.

Client / Head Contractor
Killard Excavation

Location
Harrington Grove, NSW

Length
Bore 1. 229m
Bore 2. 175m
Bore 3. 176m
580m Total

Manufacturer
Pezzimenti Laserbore™

Categories
Long Distance
Sandstone
Sewerage

PEZZIMENTI TUNNELBORE



For all inquiries – including Job Inspections,
Quotations and Project Feasibilities –
please don't hesitate to contact Pezzimenti
Tunnelbore. We are confident we'll hit the
mark on your next microtunneling project.

+ WEBSITE

www.pezzimenti.com.au

+ PHONE

61 (2) 4735 6676



When Accuracy Matters.